

NOT FOR CONSTRUCTION ISSUED FOR REVIEW & COMMENTS ONLY

existing tree to remain

proposed deciduous tree

proposed shrub

proposed perennial

existing elevation

C.I.P. concrete

snow storage area

min. 150mm topsoil, fine grade & sod

precast concrete unit pavers

REVISIONS/ SUBMISSIONS

KEY MAP - N.T.S.

LEGEND

DESCRIPTION 2024-06-20 Issued for client review Issued for submission 2024-06-25

2024-07-30 Issued for civil coordination Issued for OPA/ZBA submission 4 2024-09-18



Halton Sikh Cultural Association MUNICIPALITY Town of Oakville

PROJECT Proposed Place of Worship 2403 Khalsa Gate

MUNICIPAL FILE NUMBER

Landscape Concept

protection as required to ensure soil stabilization and proper seed

drawing and plant list, the drawing shall be considered correct.

on municipal property) from date accepted on all work unless

19. Any site plan or grading and servicing shown is for information only.

Refer to approved drawings.
20. Not for construction unless stamped, signed and dated by

21. Drawings not to be reproduced without written consent from

22. Approval of landscape plan to be obtained from municipality.

24. For grading and servicing information refer to the consulting

23. All plant material to be planted a minimum of 1.0m from any swales

25. For lighting information and power distribution refer to the electrical

18. Contractor to provide minimum one (1) year warranty (including trees

17. If discrepancies arise between plant material count shown on

16. All dimensions in meters unless otherwise noted.

germination.

otherwise specified.

Landscape Architect.

Landscape Architect.

Engineer's drawings.

consultant's drawings.

or ditches.

5. Exact locations of plant material will be determined by placement of

site services such as hydro vaults, meters, utilities roof rain water

6. All plant material locations to be staked or marked out and approved

7. Supply all plant material in accordance with the Canadian Standards

9. Supply and place mulch in accordance with Canadian Landscape

Standard (Section 10, Mulching). Disturbed soil areas around trees and shrubs are to be covered with shredded conifer bark mulch such

as 'Cedar Bark Mulch' by All Treat Farms or 'Classic Cedar Mulch' by

Gro-Bark, or approved equivalent. Alternative mulches must be

12. All support systems must be removed by the contractor at time of

final acceptance. No extras will be paid to complete this work

13. Supply and place topsoil in accordance with Canadian Landscape Standard (Section 4, Grading & Drainage and Section 6, Growing

leaders, driveways, light standards, etc.

approved by the Landscape Architect.

10. Contractor to utilize layout dimensions where provided

accommodate mature size of plant material.

11. Provide planting bed area as noted on the drawing or to

for Nursery Stock (8th ed.).

by Landscape Architect prior to installation.

8. Install plant material according to details shown.

adesso design inc. landscape architecture



69 John Street South, Suite 250 Hamilton, ON L8N 2B9 t. 905.526.8876 www.adessodesigninc.ca