


1 SITE PLAN
1 : 400



2 KEY PLAN
1 : 5000

SITE STATISTICS


TOTAL SITE AREA:	25,817.8 m ²
ROAD WIDENING AREA:	198.8 m ²
NET SITE AREA:	25,619.0 m ²
EXISTING GROSS FLOOR AREA:	10,140 m ²

ZONING COMPLIANCE:

REGULATION	BY-LAW REQUIREMENTS	EXISTING ZONING ON SITE	COMPLIANCE
MINIMUM LOT AREA	0.2ha	2.58ha	YES
MINIMUM FRONT YARD	3.0m	27.44m	YES
MINIMUM INTERIOR SIDE YARD	3.0m	16.39m	YES
MINIMUM REAR YARD	3.0m	11.89m	YES
MINIMUM LANDSCAPING COVERAGE	10%	12.3% (NO CHANGE)	YES
REQUIRED PARKING	190	236	YES

NUMBER OF PARKING SPACE:	NUMBER OF BICYCLE PARKING SPACE:
REQUIRED:	REQUIRED:
BUSINESS OFFICE	
1.0 PER 35.0 m ² NET FLOOR AREA	1.0 PER 1000 m ² NET FLOOR AREA
1.0 X 4925 / 35 = 141	1.0 X 4925 / 1000 = 5.0
WAREHOUSE	
1.0 PER 100.0 m ² NET FLOOR AREA	0.25 PER 1000 m ² NET FLOOR AREA
1.0 X 4880 / 100 = 49	0.25 X 4880 / 1000 = 1.0
TOTAL 141 + 49 = 190	5.0 + 1.0 = 6.0

PROPOSED PARKING SPACES:	PROPOSED BICYCLE PARKING SPACES:
7 BARRIER-FREE SPACES	
219 STANDARD SPACES (NOT INCLUDING 65 SPACES IN THE 14m SETBACK)	
10 LOADING SPACES	
TOTAL 236 PARKING SPACES	14



PARKING SPACE LEGEND
1 : 200

REVISION RECORD

No.	Description	Date
1	ISSUED FOR REVIEW	FEB 08, 23
2	ISSUED FOR SUBMISSION	FEB 17, 23
4	ISSUED FOR RE-SUBMISSION	OCT 13, 23

ISSUE RECORD

ALL DIMENSIONS ARE TO BE CHECKED ON-SITE BY THE CONTRACTOR. DISCREPANCIES ARE TO BE REPORTED TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

DO NOT SCALE DRAWINGS.

ALL COPYRIGHT SHALL BELONG TO THE ARCHITECT. NO PART OF THIS DOCUMENT, WHETHER IN PRINTED FORM OR SUPPLIED AS DIGITAL DATA MAY BE REPRODUCED, STORED IN A RETRIEVAL SYSTEM, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, MECHANICAL, PHOTOCOPYING, RECORDING, OR OTHERWISE WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

HOLDER OF THE CERTIFICATE OF PRACTICE:
MAR ARCHITECT INC.

STAMP



ALL OF BLOCKS 2 & 3 REGISTERED PLAN M-246.

1075 North Service Rd W,
Oakville, ON L6M 2G2

221102 As indicated RL ML
PROJECT SCALE DRAWN REVIEWED

SITE PLAN, SITE STATISTICS
A1.1