BUILDING STATISTICS			GROSS AREA		NET AREA		PARKING
A	2-STOREY BUSINESS OFFICE	40,000 SF	3,714	SQM	3,297	SQM	@1/35=94
B	2-STOREY BUSINESS OFFICE	20,536 SF	1,907	SQM	1,655	SQM	@1/35=48
B2	DAYCARE TENANT	7,750 SF	720	SQM	627	SQM	@1/40=16
C	1-STOREY MEDICAL OFFICE	7,505 SF	697	SQM	598	SQM	@1/35=17
D	1-STOREY MEDICAL OFFICE	7,505 SF	697	SQM	598	SQM	@1/35=17
E	1-STOREY SPORTS (YOGA)	5,004 SF	465	SQM	400	SQM	@1/18=22
TOTALS		88,300 SF	8,200	SQM	7,175	SQM	214

USE PERCENTAGE - NET FLOOR AREA			
BUSINESS OFFICE	4,952	SQM	69%
DAYCARE TENANT	627	SQM	9%
MEDICAL OFFICE	1,196	SQM	16%*
SPORTS (YOGA) FACILITY	400	SQM	6%
TOTALS	7,175	SQM	

*NOTE: LESS THAN 60% OF NET FLOOR AREA ON LOT

PARKING

TOTAL PARKING REQUIRED	214	
TOTAL PARKING PROVIDED	259	(+45 PARKING SPACES)
BARRIER-FREE PARKING REQUIRED	2, PLUS 2% = 8	
BARRIER-FREE PARKING PROVIDED	8	
BICYCLE PARKING REQUIRED	2 or 1/1000 SQM = 8	
BICYCLE PARKING PROVIDED	8	

COVERAGE

LOT AREA	20,224 SQM	
BUILDING COVERAGE	4,816 SQM	24%
ASPHALT SURFACE	8,365 SQM	41%
LANDSCAPE (SIDEWALKS, ETC.)	3,005 SQM	15%
LANDSCAPE (SOFT, MIN. 3mX3m)	4,038 SQM	20%

SNOW STORAGE

ASPHALT SURFACE - 8,365 SQM @ 15% =	1,255 SQM	
SNOW STORAGE PROVIDED	**850 SQM	(-37 PARKING SPACES)

**SNOWFALL IN EXCESS OF AREA PROVIDED TO BE PRIVATELY REMOVED FROM SITE

ONTARIO BUILDING CODE

BLDG A	1,982 SQM	2-STOREY	GROUP D	OBC 3.2.2.56 SPRINKLERED
BLDG B	1,407 SQM	2-STOREY	GROUP D	OBC 3.2.2.56 SPRINKLERED
BLDG C	697 SQM	1-STOREY	GROUP D	OBC 3.2.2.55 NON-SPRINKLERED, FACING 1 STREET
BLDG D	697 SQM	1-STOREY	GROUP D	OBC 3.2.2.55 NON-SPRINKLERED, FACING 1 STREET
BLDG E	465 SQM	1-STOREY	GROUP A2	OBC 3.2.2.28 NON-SPRINKLERED, FACING 2 STREETS

ZONING REGULATION (E2)	required	proposed	notes
Minimum lot area	0.2 ha	2.0 ha	20,224 SQM
Minimum lot frontage	30.0m	40.8m	Upper Middle Rd E
Minimum front yard	3.0m	5.3m	Upper Middle Rd E
Maximum front yard	n/a	n/a	
Minimum flankage yard	n/a	n/a	
Minimum interior side yard	3.0m	6.0m	Natural Area (N)
Minimum interior side yard	3.0m	6.4m	West (Farmboy)
Minimum interior side yard	3.0m	4.5m	East (Vacant)
Minimum rear yard	3.0m	4.8m	Ironoak Way
Maximum height	n/a	n/a	
Minimum landscape coverage	10%	20%	4,038 SQM

Special Provision 267

The following uses are prohibited on all lands subject to this Special Provision:

a) Motor vehicle body shop

b) Motor vehicle dealership

c) Motor vehicle repair facility

d) Motor vehicle service station



pml.A

patrick markus luckie, Architect

1283 BENDIGO CIRCLE • MISSISSAUGA, ON • L5N 1Z1 • TEL: 416 565 0159

All drawings, specifications, related document and design are the property of Patrick Markus Luckie Architect and shall be used only for the intended purpose. Reproduction of the drawings, specifications, related documents and design in whole or in part is forbidden without the written permission of Patrick Markus Luckie Architect.

This drawing, as an instrument of service, is provided by and is the property of Patrick Markus Luckie Architect and shall be used only for the specific project for which it was prepared and for delivery to this one. The contractor is responsible for the coordination and verification of all dimensions and conditions at the site and any discrepancies or conditions on site as they pertain to these documents. The contractor shall report any discrepancies to the consultant in writing prior to the commencement of any affected work.

Do not scale this drawing.
This drawing shall not be used for construction purposes unless signed by
Patrick Markus Luckie Architect

Revisions:	
Date:	Particular:
DEC.03.19	REVISED FOR 2nd SUBMISSION
JAN.27.20	REVISED FOR 3rd SUBMISSION
DEC.30.21	REVISED RAMP BLDG C

Issue:	
Date:	Particular:
SEP.16.19	ISSUED FOR SITE PLAN APPLICATION
SEP.25.19	ISSUED FOR REALTY USE
MAY.15.20	ISSUED FOR 3rd SUBMISSION
JUN.15.21	ISSUED TO CONTRACTOR
JUL.02.21	ISSUED FOR PERMIT
DEC.30.21	ISSUED FOR NOTE TO FILE
MAR.18.22	ISSUED FOR SITE PLAN – DAYCARE YARD

ONTARIO ASSOCIATION OF ARCHITECTS
PATRICK MARKUS LUCKIE
LICENCE 6742

IQ2 - SP 1506.016/01
3rd SUBMISSION

1927, 1931, 1935, 1939 and 1943 IRONOAK WAY
OAKVILLE, ONTARIO

SITE PLAN
SCALE 1:500

PROJECT No.: 19-13

A-0.1